



**ROCKFORD BOARD OF EDUCATION
INVITATION FOR BID ON SUPPLIES, MATERIALS, EQUIPMENT OR SERVICES
FOR SCHOOL DISTRICT NO. 205
ROCKFORD, ILLINOIS**

IFB No. 20-12 Lincoln M.S. Water Main Project

DATE: January 28, 2020

RE: **ADDENDUM NO. 1**

To All Bidders:

Included are modifications, clarifications and/or corrections for the Project Manual and are hereby made a part of the contract documents. Please attach this addendum to the Project Manual(s) in your possession. Please note the receipt of this addendum on the bid form. Bidders shall review changes to all portions of this work as changes to one portion may affect the work of another.

If you plan to hand deliver your IFB submission on the due date, please note you must check in on the 2nd floor prior to coming to the bid opening. Please allow time for this as late submission will not be accepted.

Refer all questions relative to the business aspect, Instructions to Bidders, Special Conditions, and questions concerning the technical aspect of the documents to the Director of Purchasing by email at purchasingdeptstaff@rps205.com.

ROCKFORD BOARD OF EDUCATION

By: Dane Youngblood
Director of Purchasing

ADDENDUM NO. 1

TO THE BID SET AND SPECIFICATIONS FOR Rockford Public Schools - Water Service Removal

Pre-Bid Date: January 27, 2020

CLARIFICATIONS

Water Service Removals

The quantity of service removals has increased by two. Abandonment of the water services to 1610 Charles Street and 1xxx 2nd Avenue have been added to the scope of work.

Pavement Removal and Replacement

Pavement removal and replacement for water service abandonment on the Vacated Street and 2nd Avenue shall be 10'x10' patch at each service location.

Pavement removal and replacement for water service abandonment on Charles Street shall be a full lane width from transverse joint to transverse joint (10.5' x 20').

Existing Water Main Sizes

Existing water main size on Charles Street is 12". The existing water mains on 2nd Avenue and the Vacated Street are 6".

END OF ADDENDUM NO. 1

Page 1 of 1
Issued: January 29, 2020
Fehr Graham



- NOTES:
1. ALL WATER SERVICES SHALL BE FIELD VERIFIED FOR DEPTH AND LOCATION.
 2. SAWCUT 10'x10' AREA FOR EACH WATER SERVICE CONNECTION LOCATED ON 2ND AVENUE AND THE VACATED STREET.
 3. SAWCUT AND REMOVE FULL LANE WIDTH FROM TRANSVERSE JOINT TO TRANSVERSE JOINT (10.5'x20') FOR EACH WATER SERVICE LOCATED ON CHARLES STREET.
 4. CORPORATION STOP SHALL BE TURNED OFF AT MAIN, WATER SERVICE LINE SHALL BE DISCONNECTED FROM MAIN, CAPPED, AND ABANDONED IN PLACE. EXISTING CURB BOXES SHALL BE REMOVED.
 5. CONCRETE REPLACEMENT SHALL BE DOWELED TO EXISTING PAVEMENT (SEE DETAIL).



FEHR GRAHAM

ENGINEERING & ENVIRONMENTAL

ILLINOIS DESIGN FIRM NO. 184-003525

ILLINOIS
IOWA
WISCONSIN

OWNER/DEVELOPER:

ROCKFORD PUBLIC SCHOOLS #205
501 7TH STREET
ROCKFORD, IL 61104

PROJECT AND LOCATION:

WATER SERVICE REMOVAL
ROCKFORD, ILLINOIS

DRAWN BY: PW
APPROVED BY: PE
DATE: 04/30/19
SCALE: AS NOTED

REVISIONS		
REV. NO.	DESCRIPTION	DATE
1	ADDENDUM #1	01/28/20

DRAWING:

PLANS

SET TYPE: OUT FOR BID

C:\30\19\19-253\19-253 Design.dwg, PLANS

JOB NUMBER:

19-253

SHEET NUMBER:

5 of 7